NOTES

- REFER TO CROSSOVER SPECIFICATION FOR GENERAL 1.) CROSSOVER REQUIREMENTS.
- BACK FILL WITH CLEAN FILL, GRAVEL OR TOP SOIL 2.) TO SUIT SURROUNDING GROUND LEVEL.
- CROSSOVER SHALL BE FREE OF ALL TRIP HAZAF 3.) AND BE DRAINED TOWARDS ROAD SURFACE, OR SUITABLY CAPTURED AND MANAGED ON PRIVA PROPERTY.
- 4.) CROSSOVER MUST BE SET BACK A MINIMUM 500 FROM EXISTING SERVICES/VEGETATION, AND A MINIMUM 1 m FROM STORMWATER SIDE ENTRY P
- CROSSOVERS SHALL BE GRADED 2.5% UP FROM 5.) OF KERB TO A POINT NO LESS THAN 2m FROM BA OF KERB. FROM THIS POINT, THE CROSSOVER CA GRADED TO MATCH EXISTING PROPERTY LEVEL
- CROSSOVERS WITH A LONGITUDINAL GRADE 6.) GREATER THAN 5% SHOULD BE AVOIDED WHERE POSSIBLE. MAXIMUM LONGITUDINAL GRADE IS 10 APPROVAL SHOULD BE SOUGHT FOR GRADES GREATER THAN 10%.

BRICK PAVING CROSSOVERS

- PAVERS SHALL BE MINIMUM 50 mm THICKNESS / 7.) BE SUITABLE FOR VEHICULAR TRAFFIC.
- HEADER COURSE SHALL BE PROVIDED ALONG EA 8.) EDGE OF CROSSOVER.
- EDGE PAVERS SHALL BE HAUNCHED WITH CONCE 9.) FILLET EDGE RESTRAINT TO RETAIN PAVERS AN REDUCE LATERAL MOVEMENT.
- 10.) PAVERS SHALL BE BEDDED ON A MINIMUM 30 mr COMPACTED SAND BLINDING LAYER ATOP A COMPACTED GRANULAR (GRAVEL OR LIMESTON BASE.

CONCRETE CROSSOVERS

- 11.) CONCRETE SHALL BE MINIMUM 150 mm THICK ON COMPACTED GRANULAR (GRAVEL OR LIMESTONE BASE.
- 12.) EXPANSION JOINTS SHALL BE PROVIDED AT BAG KERB AND WHERE CROSSOVER ABUTS EXISTING SERVICES, PATH OR OTHER INFRASTRUCTURE. EXPANSION JOINTS SHALL BE FILLED, FULL DEP WITH A POLYURETHANE SEALANT OR APPROVE SIMIL AR.
- 13.) CONTROL JOINTS SHALL BE INSTALLED AT LOCATIONS SHOWN, OR WHERE THERE IS A CHAI OF SURFACE LEVEL. CONTROL JOINTS SHALL BE FORMED WITH A SUITABLE JOINTING TOOL OR SA CUT TO A MIN DEPTH OF 1/2 THICKNESS OF CONC
- CROSSOVER SHALL BE MINIMUM 32 MPa AND BE 14.) REINFORCED WITH SL72/F72 REINFORCEMENT ME CENTRALLY PLACED.

ASPHALT CROSSOVERS

- ASPHALT SHALL BE MINIMUM 25 mm THICK DENS 15.) GRADED ASPHALT ON MINIMUM 150 mm COMPAC GRANULAR (GRAVEL OR LIMESTONE) BASE.
- TACK COAT SHALL BE APPLIED TO PREPARED 16.) GRANULAR BASE PRIOR TO INSTALLING ASPHA

GUIDELINE DRAWING SERIES 200 - CROSSOVERS

SOIL	3000 MIN.			3000 MIN.		
	6000 MAX.			6000 MAX.		
ZARDS	TRAFFICABLE		REINFORCED			
OR	BRICK PAVERS					
/ATE					FLUSH KERB	
00 mm		HEADER COL	URSE		EDGE RESTRAINT	
A						
PITS.						
ом тоі	• – <u>– – – – – – – – – – – – – – – – – –</u>				CONTROL JOINTS	
BACK			. 1000			
CAN B			1000			
ELS.			MIN.			
ERE						
10%.		$\rightarrow\rightarrow\rightarrow\rightarrow\uparrow$				
			8 / /	SPLAY SIZE TO SUIT	EXPANSION JOINT	
			2000 MIN.	DESIGN VEHICLE	ALONG KERB	
S AND						
	\mathbf{h}		REPLACE	E EXISTING KERB WITH NEW MOUN		
EACH	KERB TRANSITION TO EXIST	ING KERB	-		EXPANSIC	
			ч (I	IF EXISTING KERB IS NOT MOUNTAI	BLE)	
NCRET	F A ⊲'			B⊲→		
AND						
	BRICK PAVING CR		ſ	CONCRETE CROSSOV	FD	
		0330VLR	(CONCRETE CRUSSOV		
mm						
DNE)	TRAFF	ICABLE BRICK PAVERS				
		COMPACTED		EXPANSION JOINT	REINFORCING MESH	
		SAND BED				
DN .			=			
DNE)		1040204020402040204		<u></u>		
	<u></u>) L	H H H H H H H H H H H H H H H H H H H		
ЗАСК С		COMPACTED	MO			
NG		GRANULAR BASE	MO		COMPACTED MOI GRANULAR BASE	
					GRANDEAR BASE	
EPTH		٨				
VED	SECTION A	, – A		SECTION B-B		
IANGE						
BE		I	2000	0	GRADE TO EXISTING F	
SAW		-			<	
NCRET	Ε.		GRADE TRANS	TTION ZONE		
BE	MOUNTABLE KERB —	<				
MESH,		\mathbf{X}				
		\mathbf{X}	2.5%	6 TO ROAD		
NSE	1					
ACTED						
)	EXISTING ROAD SURFACE			GENERAL CROSSOVER GRADING PLAN		
ALT.						
	DRAWN (JY DESIGNED (JY	4				
_				SHIRE OF AUGU	ISTA MARGARET RIVER	
5			UGUSTA	STANDARD DRAWINGS		
	INFRASTRUCTURE SERVICES Orig. Size	MARGARE		SHEET TITLE		
	TECHNICAL SERVICES – WORKS A3			URBAN RESIDENT	TAL CROSSOVER DETAILS	
		i				

3000 MIN.

1

3000 MIN.

1

I

